



- ### LEGEND
- 1 L06 Asphalt paving (V: Vehicular grade)
Refer Civil Engineering Plans for details
 - 3 L06 Non-coloured in-situ concrete pavement
(as detailed and specified)
 - 2 L06 In-situ coloured concrete paving with exposed agg
Charcoal colour with saw-cut joints (2m x 2m)
(as detailed and specified)
 - 2 L06 In-situ coloured concrete paving with exposed agg
Sandy colour (V: Vehicular grade)
with saw-cut joints (2 x 2m) (as detailed and specified)
 - 3 L06 Sawn stone paver 600 x 600mm
Granite, Charcoal colour (V: Vehicular grade)
(as detailed and specified)
 - 3 L06 Stone Sett paver 90 x 90mm
Porphyry Sandy colour (as detailed and specified)
 - 3 L06 Saw-cut joint
Expansion joint
(Refer engineer's details)
 - 1 L08 Custom timber & steel seating bench
(as detailed and specified)
 - 2 L08 Custom backed timber & steel seating bench
(as detailed and specified)
 - 1 L08 Custom timber & stone seating bench
(as detailed and specified)
 - 2,3 L07 Rubbish / Recycle bin (as specified)
 - 3 L09 Bike rack
(as detailed & specified)
 - 2 L09 Handrail
(as detailed & specified)
 - 60R Removable Bollard
(as specified)
 - 7 L06 Garden bed planting
(as detailed & specified)
 - Mulch to existing trees
(as detailed & specified)
 - 9 L06 Grass - pre-grown turf
(to be installed / reinstated as specified)
*locally sourced from cold condition tolerant supplier.
 - 8 L06 Steel edge (as specified)
 - 6 L06 Advanced tree (as specified)
 - Existing tree to be retained
and protected (as specified)
 - Extent of works



NOTES

- ALL SETOUTS SHALL BE CHECKED AND APPROVED BY THE SUPERINTENDENT PRIOR TO CONSTRUCTION.
- ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE SUPERINTENDENT, WHO SHALL FURTHER ISSUE INSTRUCTIONS.
- DO NOT SCALE DRAWINGS. FIGURED DIMENSIONS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS.
- MATERIAL CODES SHALL HAVE PRECEDENCE OVER HATCHES. WHERE CODES ARE NOT SHOWN, REFER TO HATCH TYPE. WHERE DISCREPANCIES OR OMITTED DATA OCCUR, REFER TO SUPERINTENDENT FOR DIRECTION
- ALL SHOP DRAWINGS SHALL BE SUBMITTED TO THE SUPERINTENDENT FOR APPROVAL PRIOR TO FABRICATION.
- ALL FABRICATED ITEMS SHALL BE INSPECTED AND APPROVED BY THE SUPERINTENDENT PRIOR TO INSTALLATION.
- THE CONTRACTOR SHALL LOCATE ALL SUBSURFACE SERVICES ETC. PRIOR TO EXCAVATION AND PROTECT SAME DURING CONSTRUCTION.
- SERVICES LOCATION SHOWN ARE INDICATIVE ONLY. LOCATE ALL SERVICES ON SITE PRIOR TO PLANTING AND RELOCATE TREES TO 0.50M MIN. FROM SERVICES TO SUPERINTENDENTS APPROVAL.

1	ADDENDUM 1 - TEXT & JOINT CLARIFICATIONS	EB	11.11.16
0	TENDER ISSUE	EB	07.10.16
B	Issue for Council review	ESR	16.09.16
A	preliminary issue to Council	EB	26.08.16

REV. | DESCRIPTION | REF. | DATE

MDG Landscape Architects
Level 2, 45 Victoria Avenue
Albert Park, Victoria 3206 Australia
T: (03) 9696 4957
F: (03) 9696 5594
E: mail@mdgls.com.au

ALPINE BETTER PLACES

ALPINE

DRAWING TITLE
BRIGHT
Set-out, Materials and Finishes Plan

DATE	SCALE
June 2016	1:200 @ A1, 1:400 @ A3
FILE PATH	DRAWING
J:\1510 Alpine Shire Concepts\6. Documentation\1510 Alpine L01	EB
CHECKED	DESIGN
AM	EB
DRAWING NO.	REVISION
1510B L02	1